



135th Street Improvement Project from M-150 to Holmes Road

Project Facts:

- Length = 5,800 feet of Improved Roadway
- Three Lane Secondary Arterial (with Center Turn Lane)
- New Curb & Gutters
- New on-street parking (55 parallel parking spaces)
- New ADA Compliant Sidewalks (both sides of Road)
- Enclosed Underground Storm Drainage System
- New Water Line
- New Street Lighting
- Traffic Signals
 - Wornall (New)
 - Washington/Inverness (Modified)
 - Holmes (Modified)

Project Schedule:

- Preliminary Plans have been reviewed by the City/County.
- Right-of-way plans can be complete by middle of October 2011.
- Final Design can be complete by May 2012.
- Right-of-way Acquisition – January - April 2012
- Ready for bidding by Fall 2012.

Project Costs:

Engineering Costs

Preliminary Design	& R/W	= \$ 263,400 (by Jackson Co.)
R/W Appraisals & Final Design		= <u>\$ 269,430</u> (\$100,000 by KCMO)
		(\$169,430 by MC-CID)
Total Engineering		= \$ 532,830

Construction Cost = \$5,800,000

**All funding numbers have been coordinated with the
Kansas City Missouri Public Works and City Planning Staff
(MC-CID will contribute to cost of Landscape, Streetscape and other Enhancements)**